

**RISKS OF INADEQUACIES OF INPUTS OF
PRECONSTRUCTION ACTIVITIES TO
DESIGN PHASE ON COST AND TIME OVERRUNS
IN CONSTRUCTION PROJECTS**

Leelanath Daluwatte

168040P

Degree of Doctor of Philosophy

Department of Civil Engineering

University of Moratuwa

Sri Lanka

March 2021

**RISKS OF INADEQUACIES OF INPUTS OF
PRECONSTRUCTION ACTIVITIES TO
DESIGN PHASE ON COST AND TIME OVERRUNS
IN CONSTRUCTION PROJECTS**

Leelanath Daluwatte

168040P

Dissertation submitted in partial fulfilment of the requirement for the Degree of
Doctor of Philosophy

Department of Civil Engineering

University of Moratuwa

Sri Lanka

March 2021

DECLARATION

“I declare that this is my own work and this dissertation does not incorporate without acknowledgement any material previously submitted for a Degree or Diploma in any other University or institute of higher learning and to the best of my knowledge and belief it does not contain any material previously published or written by another person except where the acknowledgement is made in the text.

Also, I hereby grant to University of Moratuwa the non-exclusive right to reproduce and distribute my dissertation, in whole or in part in print, electronic or other medium. I retain the right to use this content in whole or part in future works (such as articles or books).

Signature:

Date:23-03-2021

The above candidate has carried out research for the PhD thesis Dissertation under my supervision.

Name of the supervisor: Professor Malik Ranasinghe

Signature of the supervisor:

Date : 23-03-2021

ABSTRACT

Cost and Time overruns are common occurrences in construction projects completed in Sri Lanka. This research study was carried out to find the possible reasons for these overruns. The objectives of the study were to review, identify and analyze risks created by the inadequacies, correlations, coherence and accuracy of the input data of pre-construction activities to the design phase of construction projects and to develop and validate an industry best practice framework/model/guideline to minimize/eliminate cost and time overruns of construction projects due to risks of inadequacies, correlations, coherence and accuracy of the inputs of pre-construction activities to the design phase of the projects.

Initially, contributory factors for Cost and Time overruns of construction projects were identified. 'Design effects' was found to be the critical contributory factor. A study on 'Design effects' identified the pre-construction activities that are input to the design phase of construction projects. These pre-construction activities were used to examine 'Relevance of the activity' and 'Adequacy of the input of the activity' to the design phase in a construction project. Accordingly, a model, " $z = 100 - 2.6916e^{0.024x}$ " where 'Inadequacy of the input to the design phase (z)' and 'Relevance of a pre-construction activity (x)' was derived for the input of a pre-construction activity to design phase of a construction project.

Pre-construction activities were expanded and analysed to assess the risks created by inadequate inputs from the pre-construction activities to the design phase of construction projects as follows. Scientifically developed questionnaires based on the mixed type of research method and where internal consistency was rated as 'excellent' were used for data collection. The probabilistic random sampling method confirmed that the sample of respondents selected for the study was adequate. One questionnaire was used to collect data from 32 projects to examine 'Relevance' and 'Adequacy' of input from pre-construction activities to the design phase of construction projects. The other questionnaire was used to collect data from 100 projects to examine the possibility of eliminating/minimising the Risk of Cost overruns and Risk of Time overruns by retaining services of a third-party independent designer to verify the adequacies of input from preconstruction activities to the design phase of construction projects. All respondents to the questionnaires were substantive experts actively involved in construction projects.

A structure to collect data was developed to identify and analyze risks from the input of respective pre-construction activities to the design phase of construction projects. The developed framework analysed risks using Risk Matrix, Relative Importance Index (RII), Severity Index (SI), Descriptive Statistics, Sampling Adequacy, Reliability, Validity, Correlation and Accuracy of data, Biases, Coherence of responses and Calibration of respondents.

Guideline for industry best practice was derived by using scientific techniques of data analysis for risks created by the inadequacies of input from respective pre-construction activities to the design phase of construction projects. Results from the analysis satisfied the limits set by each scientific technique used for the analysis. The analysis highlighted the ranks of preconstruction activities which with inadequate input to the design phase of construction projects increased the Risk of exceeding Cost, Risk of exceeding Time and minimising the Risk of exceeding Cost and Time. Risk interpretation revealed that top ranks of preconstruction activities were 'Likely' to induce Risk of exceeding Cost and Risk of exceeding Time of construction projects.

Guideline for industry best practice was validated through statistical methods and Case studies from the construction industry. The main conclusions of the study were that: i) Inadequacies of input from preconstruction activities to the design phase contributed towards Cost overruns and Time overruns in construction projects; ii) Risks created by the inadequacies, correlations, coherence and accuracy of the input data of pre-construction activities to the design phase of construction projects contributed towards Cost overruns and Time overruns in construction projects and iii) Verification of the input from preconstruction activities to the design phase of construction projects by a third party independent designer would minimise the Risk of exceeding Cost and the Risk of exceeding Time of Construction projects. In addition to the 3 main conclusions described above, there were 19 conclusions and 3 recommendations.

Key words: Cost overrun, Time overrun, Preconstruction activities, Risk, Independent designer

This dissertation is dedicated with warmest gratefulness to

my School

Ananda College, Colombo, Sri Lanka

and

my University

University of Moratuwa, Sri Lanka.

These two institutions paved the way for me to be what I am today.

ACKNOWLEDGEMENT

I express my heartfelt gratitude to Professor Malik Ranasinghe, my supervisor, who made the study stimulating and enjoyable. I greatly appreciate his availability for the study, almost at any time, prompt responses, guidance, advice, feedback and support from the inception of the study. I am blessed to have him as my supervisor.

I also thank Professor Asoka Perera and Dr S B Wijekoon, members of the review panel and Professor Saman Bandara for the valuable inputs given during the study. In addition, input to the study from Professor Kamal Premaratne, Dr. Asitha Seneviratne and Dr. Vasantha Abeysekara is deeply appreciated.

Further, noteworthy support to the study given by Mr. Namal Peiris, Mr. Sisira Weerabahu, Ms. Dinusha de Silva, Mr. Isuru Herath, Ms. Sashenka Kumarage, Ms. Dinusha Dissanayake, Mr. Thushara Perera, Mr. Darshana Weerabahu and Mr. Barnes Abeywardena is highly appreciated. Also, my appreciation goes to the experts who positively reacted to the requests for responses related to the study. In addition, I appreciate the relevant staff of the University of Moratuwa, specially from the Faculty of Graduate Studies for giving the best possible support to the study.

The encouragement given in either way to the study by my son, Randesh Daluwatte, was probably one of the highlights of the process of the study and I really appreciate his sincere efforts. Finally, I like to thank my family for standing by me.

TABLE OF CONTENTS

COVER PAGE.....	i
TITLE PAGE	ii
DECLARATION	iii
ABSTRACT.....	iv
DEDICATION	v
ACKNOWLEDGEMENT	vi
TABLE OF CONTENTS	vii
LIST OF FIGURES	xiii
LIST OF TABLES	xiv
APPENDICES	xvi
CHAPTER 1– INTRODUCTION	1
1.1 Background	1
1.2 Research Problem.....	1
1.3 Research Aim	2
1.4 Research Objectives	2
1.5 Main Findings.....	2
1.6 Structure of the Thesis.....	3
CHAPTER 2 - LITERATURE REVIEW	5
2.1 General	5
2.2 Cost and time overruns of construction projects	5
2.2.1 Stakeholder Contribution.....	5
2.2.2. Pre-construction Conditions	5
2.2.3. Finance.....	7
2.2.4. Approvals.....	8
2.2.5. Project communication	8
2.2.6. Contract conditions	9
2.2.7. Bid.....	9
2.2.8. Design	9
2.2.9. Planning	10
2.2.10. Workers.....	12
2.2.11. Material	12
2.2.12. Management.....	14
2.2.13. Contract Management.....	14
2.2.14. Site conditions.....	15

2.2.15. Site management.....	15
2.2.16. Delay in decisions.....	16
2.2.17. Payments to Contractor.....	16
2.2.18. Change order requests.....	16
2.2.19. Contractor inexperience.....	17
2.2.20. Changes by Client.....	17
2.2.21. Changes in Scope.....	18
2.2.22. Construction methods.....	19
2.2.23. Construction Technology.....	19
2.2.24. Government policies.....	20
2.3 Pre-construction phase of construction projects.....	20
2.3.1 Pre-construction approach.....	20
2.3.2 Pre-construction activities.....	20
2.3.3 Pre-construction planning.....	21
2.3.4 Design and pre-construction phase.....	22
2.3.5 Project control in pre-construction phases.....	22
2.4 Inadequacies of inputs to design phase.....	22
2.5 Risks and risks of inadequacies.....	22
2.5.1 Overview.....	22
2.5.2 Risk identification.....	23
2.5.3 Risk Quantification.....	23
2.5.4 Risk Matrix.....	24
2.5.5 Risks in projects.....	25
2.5.6 Risk Response.....	25
2.5.7 Risk Management.....	26
2.5.8 Proactive approach in managing risk.....	26
2.6 Correlation.....	27
2.7 Calibration.....	28
2.8 Coherence.....	29
2.9 Accuracy.....	31
2.10 Bias.....	31
2.11 Accuracy and Bias.....	32
2.12 Research methodology.....	32
2.13 Likert scale.....	32
2.14 Substantive Experts.....	33
2.15 Summary.....	33
CHAPTER 3 – RESEARCH METHODOLOGY.....	35

3.1 General	35
3.2 Research Methods	35
3.3 Selection of the Research Methods	37
3.4 Analysis and Methods used in the study	38
3.4.1 Descriptive Analysis	38
3.5 Selection of an appropriate research method	38
3.5.1 Qualitative research method	38
3.5.2 Quantitative research method	39
3.5.3 Mixed research method.....	39
3.6 Methodology for the development of a questionnaire for different research methods ...	40
3.6.1 Methodology for the development of a questionnaire for the qualitative research method	40
3.6.2 Methodology for development of a questionnaire for the quantitative research method	41
3.6.3 Methodology for development of a questionnaire for the mixed research method ...	41
3.7 Population and Sampling methods	41
3.7.1 Sequence to determine sampling size;	41
3.7.2 Sampling techniques – Qualitative method	41
3.7.3 Sampling techniques – Quantitative method	42
3.7.4 Calculation of sample size – Formulae, Tables and Calculators	42
3.8 Flowcharts of the Research Methodology	43
3.9 Validation of the guideline developed from the study	47
3.9.1 Validation using testing Hypothesis	47
3.9.2 Validation using case studies from the construction industry	47
3.10 Summary	47
CHAPTER 4 - DEVELOPMENT OF THE ANALYSIS FRAMEWORK	48
4.1 General	48
4.2 Risks Created by the Inadequacies of Inputs.....	48
4.2.1 Risks.....	48
4.2.2 Pre-construction Activities	49
4.2.3 Inadequacy of Inputs.....	53
4.3 Risk Matrix.....	53
4.4 Likert Scale.....	53
4.5 Accuracy.....	54
4.6 Bias	55
4.7 Coherence	55
4.7.1 Coherence in Respondent	55

4.7.2 Coherence in Data.....	55
4.8 Calibration	57
4.9 Correlation.....	57
4.10 Substantive Experts	57
4.11 Questionnaire design	58
4.12 Expected Outcome	59
4.12.1 Risk Rating	59
4.12.2 Risk of Exceeding Cost/Time:.....	60
4.12.3 Critical Pre-construction Activities	61
4.12.4 Risk Interpretations.....	61
4.13 Summary	61
CHAPTER 5 – DATA COLLECTION	63
5.1 General	63
5.2 Contributory factors and pre-construction activities used for data collection.....	64
5.2.1 Contributory factors.....	64
5.2.2 Pre-construction Activities to find the relationship between Relevance and Adequacy.	66
5.2.3 Pre-construction Activities to find the Risk created by input to the design phase	68
5.3 Development of Questionnaires for Data Collection	69
5.3.1 Development of Questionnaire for 38 pre-construction activities.....	69
5.3.2 Pilot survey for the Questionnaire with 38 pre-construction activities	69
5.3.3 Development of Questionnaire for 49 pre-construction activities.....	71
5.3.4. Pilot survey for the Questionnaire with 49 pre-construction activities	71
5.4 Finalised Questionnaire of the 38 pre-construction activities	71
5.5 Finalized Questionnaire with 49 pre-construction activities	72
5.6 Collection of data for contributory factors and pre-construction activities.....	72
5.6.1 Collection of data for contributory factors	72
5.6.2 Collection of data for 38 pre-construction activities	72
5.6.3 Collection of data for 49 pre-construction activities	74
5.7 Summary	75
CHAPTER 6 – DATA ANALYSIS.....	76
6.1 General	76
6.2 Analysis of contributory factors for cost and time overruns	76
6.3 Effects of the inputs to pre-construction activities in the design phase of construction projects	78
6.3.1 Preliminary Analysis.....	78
6.3.2 Relationship between Relevance and Adequacy of pre-construction activities	79

6.3.3 Relationship between Relevance and input of pre-construction activities 100% adequate to the design phase of construction projects.....	82
6.4 Methods used for Data analysis.....	84
6.4.1 Data analysis for the qualitative research method	84
6.4.2 Data analysis for the quantitative research method	84
6.4.2.1 Reliability analysis.....	84
6.4.2.2 Relative Importance Index (RII).....	85
6.4.2.3 Severity Index (SI).....	85
6.4.2.4 Sampling adequacy	86
6.5 Risks created by Inadequacies, Correlations, Coherence, Accuracy, etc.....	86
6.5.1 Background.....	86
6.5.2 Development of the Questionnaire	86
6.5.3 Risk Rating	88
6.5.4 Risk of Exceeding Cost/Time and minimising the Risk of exceeding Cost and Time by a third-party independent designer	89
6.5.5 Critical Pre-Construction Activities.....	93
6.5.6 Risk Interpretations.....	96
6.5.7 Analysis of the data set using the Relative Importance Index (<i>RII</i>)	100
6.5.8 Analysis of the Data set using Severity Index (<i>SI</i>)	104
6.5.9 Analysis of the data set using Descriptive Statistics.....	107
6.5.10 Analysis of the data set for Reliability.....	109
6.5.11 Analysis of Validity of data	110
6.5.12 Correlation analysis	113
6.5.13 Sampling Adequacy.....	115
6.6 Observations made from the results of the analysis	116
6.7 Best practice Guideline developed based on the outcome of the analysis	122
6.8 Summary	122
CHAPTER 7 - VALIDATION OF THE DEVELOPED GUIDELINE	124
7.1 General	124
7.2 The Guideline	124
7.3 Validation using testing Hypothesis.....	124
7.3.1 Null Hypothesis, H_0 :.....	125
7.3.2 Alternative Hypothesis, H_1 :	126
7.3.3 Testing of hypothesis.....	126
7.3.3.1 Results of the hypothesis testing of ‘Risk of exceeding Cost’ and ‘Minimising Risk of exceeding Cost and Time’ by verification by a third party independent Designer.....	127
7.3.3.2 Results of the hypothesis testing of ‘Risk of exceeding Time’ and ‘Minimising Risk of exceeding Cost and Time’ verification by a third party independent Designer.....	128

7.4 Validation using Case Studies from the construction industry	129
7.4.1 General	129
7.4.3 Categorization of ‘Issues’ identified as contributing towards exceeding Cost and exceeding Time after projects.	130
7.4.4 Project-specific Uncontrollable ‘Issues’ for Project A, Project B and Project C.....	135
7.4.5 Project-specific Controllable ‘Issues’ for Project A, Project B and Project C.....	136
7.4.6 Categorization of Controllable issues of projects.....	137
7.4.6.1 Examination if the Controllable Issues were generated at the Design phase of projects.....	137
7.4.6.2 Comparison of Controllable ‘Issues’ that cause Cost and Time overruns <i>and</i> Preconstruction activities that provide inputs to the design phase of projects.	142
7.5 Summary	147
CHAPTER 8 – CONCLUSIONS and RECOMMENDATIONS	148
8.1 General	148
8.2 Conclusions	148
8.3 Recommendations for future work.....	152
REFERENCE LIST	154
APPENDICIES	167

LIST OF FIGURES

<i>Figure 1</i> - Quantifying risk: measuring the invisible.....	24
<i>Figure 2</i> - Calibrating the human instrument.....	29
<i>Figure 3</i> –Qualitative, quantitative and mixed research methods.....	40
<i>Figure 4</i> – Flow chart for analysis of design inputs from a preconstruction activity. ...	44
<i>Figure 5</i> – Flowchart for Cost and Time overruns in construction projects	45
<i>Figure 6</i> – Flow chart for possible generation of errors in construction projects.....	46
<i>Figure 7</i> - Risk Rating of a Pre-construction activity.	59
<i>Figure 8</i> - Quantification of Risk of a Pre-construction Activity.	60
<i>Figure 9</i> - Risk rating and quantification of Risk for a Pre-construction activity	61
<i>Figure 10</i> - Part of the questionnaire of relevant thirtyeight preconstruction activities .	73
<i>Figure 11</i> - Part of the questionnaire of relevant forty-nine preconstruction activities ..	74
<i>Figure 12</i> - Three highest contributory factors for Cost and Time overruns of construction projects.	77
<i>Figure 13</i> - Seven highest contributory factors for Cost and Time overruns of construction projects.	78
<i>Figure 14</i> – Relationship of Relevance (%) and Inadequacy (%) of a preconstruction activity.....	84
<i>Figure 15</i> - Part of Responses to the Questionnaire for the forty-nine preconstruction activities	87
<i>Figure 16</i> - Risk rating, Risk of exceeding Cost and Time due to an inadequate input of a preconstruction activity	89
<i>Figure 17</i> - Limits of the shifted normal distribution for equal probabilities	97
<i>Figure 18</i> - ‘p’ value and statistical significance	125

LIST OF TABLES

Table 1 – Calibration of the human instrument	28
Table 2 - Questions to consider when developing qualitative studies.	30
Table 3 - Eight Research Methods	35
Table 4 - Research Method Classification	36
Table 5 - Mixed Research Method.....	37
Table 6 - Options considered to start the process of the study.....	43
Table 7 – Derivation of Forty-nine relevant pre-construction activities.....	49
Table 8 - Questions to consider in developing a qualitative questionnaire.....	56
Table 9 - Contributory factors for cost and time overruns of construction projects	65
Table 10 - Relevant Thirty-eight Pre-construction Activities.....	67
Table 11 - Relevant Forty-nine Pre-construction Activities.	68
Table 12 - Sum and % Contribution of Top-Ranking Factors towards overruns.	77
Table 13 – Relevance and Adequacy of 12 preconstruction activities of 18 Projects ...	79
Table 14 – Relevance and Adequacy of 38 preconstruction activities of 32 projects ...	80
Table 15 - Results of the Regression analysis.....	83
Table 16 - Risk Estimates of preconstruction activities; Cost, Time and Designer.....	90
Table 17- Top Ten Critical pre-construction activities to Risk of exceeding Cost.....	93
Table 18 - Top Ten Critical pre-construction activities to Risk of exceeding Time.....	94
Table 19 - Minimising Risk of exceeding Cost and Time by an Independent Designer.....	95
Table 20 - Top five ‘Identical’ preconstruction activities for ‘Cost’ and ‘Time’	95
Table 21- Top Ten pre-construction activities for Risk of exceeding ‘Cost’ and ‘Time’	96
Table 22 - Ranges for Risk Interpretation.....	97
Table 23 – Interpretation of Risk of exceeding the ‘Cost’	98
Table 24 - Interpretation of Risk of exceeding the ‘Time’	98
Table 25 – Interpretation of Risk of ‘Minimising the Risk of exceeding Cost and Time’	99
Table 26- Number of pre-construction activities in Ranges of Risk interpretation	100
Table 27 - RII values of Top Ten preconstruction activities inducing Risks.....	101
Table 28 - RII values of ‘Impact’, ‘Likelihood’, ‘Cost’ and ‘Time’ categories	102
Table 29 - RII values for ‘Minimising the Risk of exceeding Cost and Time’	103
Table 30 – SI values of pre-construction activities for ‘Time’	104
Table 31 - SI values of ‘Impact’, ‘Likelihood’, ‘Cost’ and ‘Time’ categories	105
Table 32 – SI values for ‘Minimising the Risk of exceeding Cost and Time’.....	106
Table 33 - Mean score and Standard Deviation of ‘Impact of Risk’.	108
Table 34 – Mean score and Standard Deviation of ‘Minimising the Risk of exceeding Cost and Time’.....	108
Table 35 – Results of Reliability (Cronbach’s alpha) analysis	110
Table 36 - Validity analysis for ‘Risk of exceeding Cost’	111
Table 37 – Validity analysis: ‘Lowest’ values of category ‘Impact’	112
Table 38 – Validity analysis: 10 ‘Lowest’ values of the category ‘Minimising the Risk of exceeding Cost and Time’	113
Table 39 - Pearson correlation values for the category of ‘Impact of Risk’	114
Table 40 - Pearson correlation values for ‘Minimising the Risk of exceeding Cost and Time’.....	115
Table 41 - Kaiser-Meyer-Olkin (KMO) sampling Adequacy of the data set.	116

Table 42 - ‘p’ test values of ‘Minimising Risk of exceeding Cost’	127
Table 43 - ‘p’ test values of ‘Minimising Risk of exceeding Time’	128
Table 44 - ‘Issues’ contributed to exceeding ‘Cost’ and ‘Time’ - Project A.....	131
Table 45 - ‘Issues’ contributed towards exceeding ‘Cost’ and ‘Time’- Project B.....	132
Table 46 - ‘Issues’ contributed towards exceeding ‘Cost’ and ‘Time’- Project C.....	134
Table 47 - Uncontrollable ‘Issues’ created ‘Cost’ and ‘Time’ overruns in Projects ...	135
Table 48 – Summary of Overruns due to Controllable Issues in Projects.	137
Table 49 - Links of Controllable ‘Issues’ <i>and</i> Pre-construction activities-Project A..	138
Table 50 - Links of Controllable ‘Issues’ <i>and</i> Pre-construction activities-Project B. .	139
Table 51 - Links of Controllable ‘Issues’ <i>and</i> Pre-construction activities-Project C..	141
Table 52 – Comparison of Controllable ‘Issues’ of Projects and ‘Preconstruction activities’	143

APPENDICES

Annexure - 1: Questionnaire used for the survey of <i>thirty-eight</i> preconstruction activities.	167
Annexure 2 - Questionnaire used for the survey of <i>forty-nine</i> preconstruction activities.	169
Annexure - 3: Sample of the response of survey of 100 projects.	170
Annexure - 4: Risk estimates of <i>forty-nine</i> pre-construction activities.....	171
Annexure - 5: Risk of Exceeding Cost due to Inadequate Inputs	174
Annexure - 6: Risk of Exceeding Time due to Inadequate Inputs	176
Annexure - 7: Interpretation of Risk of exceeding Cost due to Inadequate Inputs.....	178
Annexure - 8: Interpretation of Risk of exceeding Time due to Inadequate Inputs.....	180
Annexure - 9: Results of RII analysis of forty-nine preconstruction activities.....	182
Annexure - 10: Results of SI analysis of forty-nine preconstruction activities.	185
Annexure - 11: Results of Descriptive Statistics analysis for category ‘Cost’.	188
Annexure - 12: Results of Descriptive Statistics analysis for category ‘Time’	190
Annexure - 13: Results of Validity analysis for the category ‘Cost’.	192
Annexure - 14: Results of Validity analysis for the category ‘Time’.	194
Annexure - 15: Results of Pearson coefficient for the category of ‘Cost’.	196
Annexure - 16: Results of Pearson coefficient for the category of ‘Time’.	201
Annexure - 17: ‘p’ values for ‘Minimization of Risk of exceeding Cost using IBM SPSS Analysis.....	206
Annexure - 18: ‘p’ values for ‘Minimization of Risk of exceeding Cost using Microsoft Excel 2019.....	210
Annexure - 19: ‘p’ values for ‘Minimization of Risk of exceeding Time using IBM SPSS Analysis.....	211
Annexure - 20: ‘p’ values for ‘Minimization of Risk of exceeding Time using Microsoft Excel 2019.....	215