

RESOURCE OPTIMIZATION WITH THE USE OF PRECAST SLAB SYSTEMS

Kekallele Gamachchige Janaka

(158963M)

Dissertation submitted in partial fulfilment of the requirements for the Degree
Master of Science

Department of Civil Engineering

University of Moratuwa
Sri Lanka

August 2019

DECLARATION OF THE CANDIDATE AND SUPERVISOR

I declare that this is my own work and this dissertation does not incorporate without acknowledgement any material previously submitted for a Degree or Diploma in any other University or institute of higher learning and to the best of my knowledge and belief it does not contain any material previously published or written by other person except where the acknowledgement is made in the text. Also, I hereby grant to University of Moratuwa the non-exclusive right to reproduce and distribute my dissertation, in whole or in part in print, electronic or other medium. I retain the right to use this content in whole or part in future works (such as articles or books).

K.G.Janaka

Date: 02nd August 2019

The above candidate has carried out research for the Masters dissertation under my supervision

Professor (Mrs.) C. Jayasinghe

Date: 02nd August 2019

ACKNOWLEDGEMENTS

Foremost, I would like to express my sincere gratitude to my supervisor Professor (Mrs.) Chinth Jayasinghe, Senior Professor, Department of Civil Engineer, the University of Moratuwa for the continuous support and guidance given for the course of research study, for their patience, Motivation, enthusiasm and immense knowledge. Their guidance helped me in all the time of research and writing of this dissertation.

I would also like to extend my thanks to the course coordinators Prof. Asoka Perera and Dr. L.L.Ekanayake and all other lectures and staff members of the Department of Civil Engineering University of Moratuwa for the support given me during a reading of my MSc.

I take this opportunity to extend my thanks to Eng. Rohana de Silva, Design Advocacy (Pvt) Ltd. for the introduction of Special Precast slab system based to this study and I would like to thank my office and project staff of Central Engineering Consultancy Bureau (CECB) for the flexibility and encouragement to me.

It is a great pleasure to remember my loving family wife and Childs, Parents for supporting me spiritually throughout my life and tolerating my engagement on this work

K.G.Janaka

ABSTRACT

Resource optimization is one of the key themes of sustainable development. With the fast growing construction industry over the past few decades, the consumption of natural resources has been on the rise. Rapid urbanization in Sri Lanka demands more and more multistoried buildings, resulting in a large quantity of resource utilization. The slab system which consumes lots of material and time is a key element of multi-storied structures. The slab system also creates the highest amount of construction waste to the environment. Therefore, the research covered in this paper has been focused on a novel slab system developed with optimized resource utilization.

The proposed slab system comprised of a pre-cast plank system designed as a hollow slab consisting of 60 mm thick precast concrete panel, lightweight filler material using compressed straw boards and an in-situ screed concrete layer on top. The precast pael of 5 m span and 1.2 m wide consist of two trusses and BRC mesh.

The proposed slab system optimizes material consumption in the form of false work, formwork. The reusable steel mold used as formwork eliminates the use of timber and plywood. Erecting and assembling the proposed pre-cast system will consume much less time compared to that of in-situ construction. Steel shutters will create a better surface finish so that the systems need less labour and material for the application of finishing coats. Pre-stressing of the slab can further optimize the system by reducing reinforcement requirement.

The propose slab system can promote cost effective construction with optimized use of materials and labour resulting in faster construction and higher quality of the end product compared to the conventional slab system. Reuse of waste products such as paddy straw as a filler material and also reusing steel molds will further enhance the life cycle cost in the form of environmental benefits.

Keywords: Precast concrete; Slab construction, Resource optimization, Sustainability

TABLE OF CONTENTS

DECLARATION OF THE CANDIDATE AND SUPERVISOR.....	ii
ACKNOWLEDGEMENTS.....	iii
ABSTRACT.....	iv
CHAPTER 01	
INTRODUCTION	1
1.1. Background	2
1.2. Research Problem.....	3
1.3. Objectives.....	3
1.4. Research Methodology.....	4
1.5. Limitations of the Study.....	5
CHAPTER 02	
LITERATURE REVIEW	6
2.1. General.....	6
2.2. Environmental Impact.....	7
2.3. International Context	10
2.4. Comparative Studies on Precast and Conventional Construction Methods....	12
2.5. Sri Lankan Approach	19
2.6. Summary of the Literature Survey.....	21
CHAPTER 03	
RESEARCH METHODOLOGY.....	23
3.1. General.....	23
3.2. Research Approach	23
3.3 Selection of Projects	24
3.4. Sources of Data Collection	28
CHAPTER 04	
DATA ANALYSIS AND RESULTS.....	29
4.1. Precast Plank Slab Construction Technology	29
4.1.1. Design of precast plank slab	29

4.1.2. Fabrication	31
4.1.3. Transportation and lifting.....	32
4.1.4. Supports and installation.....	33
4.1.5. In-situ cast top layer.....	34
4.1.6. Soffit surface finishing.....	35
4.2. Conventional In-Situ Cast Slab Technology.....	38
4.2.1. False work system.....	39
4.2.2. Form work.....	39
4.2.3. Slab Reinforcement and concreting	40
4.2.4. Soffit surface Finishing.....	40
4.2.5. Quantity analysis of resources	41
4.3. ICC Suspended Beam Slab System (SBS).....	43
4.3.1. Form Work System	43
4.3.2. Topping concrete	44
4.3.3. Quantity analysis of resources	44
4.4. Comparative Analysis on Resources	45
4.5. Cost Comparison.....	47
4.6. Construction Time Comparison.....	49
 CHAPTER 05	
CONCLUSION AND RECOMMENDATION.....	51
5.1. Conclusion	51
5.2. Recommendation	53
REFERENCES	55

LIST OF FIGURES

Figure 2.1: Life Cycle CO2 emission and Solid waste Generation of each constrcution Technology.....	7
Figure2.2: Estimated Cost and Time for Conventional, Monolithic and Precast Construction.....	15
Figure 2.3: Cross section of NERD slab system.....	19
Figure 2.4: Cross section of ICC Easy Slabs	20
Figure 2.5: Cross Section of ICC SBS System	20
Figure 3.1: Flow Chart- Research Methodology	24
Figure 4.1: Cross sectional detail of precast plank slab.....	29
Figure 4.2: Longitudinal section of precast plank slab panel	30
Figure 4.3: Cross section of precast plank slab panel.....	30
Figure 4.4: Lattice Girder.....	31
Figure 4.5: Curing of Precast Plank Slab panel and Steel Molds used in Hambantota Project for precast plank slab fabrication.....	31
Figure 4.6: Ground Reservation for panel casting and Mold used in Nuwara Eliya project within the tanks.....	32
Figure 4.7: Slab Panel Transport arrangement and Slab Panel Stacking System	33
Figure 4.8: Slab Panel Hanging Device and Slab Panel Lifting by tower crane	33
Figure 4.9: Supporting system and placing method on main beams of precast plank slab panels.....	34
Figure 4.10: Straw Boards and Straw board laying on Precast Slab	34
Figure 4.11: Preparation for topping concrete and Topping concrete pouring.....	35
Figure 4.12: Bottom surface appearance and finished slab soffit.....	35
Figure 4.13: Load testing for sample slab.....	36
Figure 4.14: Load testing for Precast Palnk Salb panel at site.....	36
Figure 4.15: Selected Floor Slab are, Hambantota New District General Hospital (Project 01).....	38
Figure 4.16: Selected Floor Slab, Nuwara Eliya New District General Hospital (Project 02).....	38

Figure 4.17: Supporting System of Conventional Slab.	39
Figure 4.18: Form work of conventional slab.....	40
Figure 4.19: Reinforcement for conventional slab and Concrete pouring using pump car.....	40
Figure 4.20: Selected Slab area of Nephrology dialysis center project (Project 01) .	41
Figure 4.21: Selected Slab area of Pediatric Unit project (Project 01).....	42
Figure 4.22: T-Beam Installation at site and Cement Block Installation at site	43
Figure 4.23: Arrangement for Topping concrete and pouring of 50mm thick concrete layer.....	44
Figure 4.24: Cost of Slab Construction.....	50
Figure 4.25: Time for Slab Construction	50

LIST OF TABLE

Table 2.1: Benefits of prefabrication	10
Table 3.1: New District General Hospital Building – Hamabntota (Project 01)	25
Table 3.2: New District General Hospital Building - Nuwara Eliya (Project 02)	26
Table 3.3: Nephrology Dialysis and Transplant Unit, General Hospital, Karapitiya (Proj. 01)	26
Table 3.4: Specialized Pediatric Unit, General Hospital, Karapitiya (Project 02).....	27
Table 3.5: Commercial Building For Mr. L.I.S Perera, Nugegoda (Project 01).....	27
Table 3.6: Commercial Building for Welikala Holdings, Nawala (Project 02).....	27
Table 4.1: Material Quantities of standard precast plank slab Panel	31
Table 4.2: Quantities of resources utilized for precast plank slab	37
Table 4.3: Quantities of resources utilized for Conventional Slab	42
Table 4.4: Quantities of resources utilized for ICC SBS system.....	45
Table 4.5: Comparison of resource utilized for 100m ² area of each slab system.....	46
Table 4.6: Cost calculation of 100m ² area of Precast Plank Slab	48
Table 4.7: Cost calculation of 100m ² area of Conventional Slab	48
Table 4.8: Cost calculation of 100m ² area of ICC SBS	49
Table 4.9: Time consumed for construction of 100m ² slab area of each slab system	50

LIST OF ABBREVIATIONS

Abbreviation	Description
ICC	International Construction Consortium
SBS	Suspended Beam Slab
NERD	National Engineering Research and Development
GDP	Gross Domestic Product
ADPT	Analytical Design Planning Technique
GI	Galvanized Iron
CECB	Central Engineering Consultancy Bureau
BRC	British Reinforcement Company
SKL	Skilled Labour
USKL	Unskilled Labour
NDT	Nephrology Dialysis and Transplant
SLS	Sri Lankan Standard
CS	Conventional Slab
PPS	Precast Plank Slab

LIST OF APPENDICES

Appendix	Description	Page
Appendix – A	Structural Drawing. (HB/ST/22/T).....	57
Appendix – B	General Arrangement Drawing 2 nd Floor Hambantota General Hospital Building.....	58
Appendix – C	General Arrangement Drawing 2 nd Floor Nuware Eliya General Hospital Building.....	59
Appendix – D	General Arrangement Drawing, NDT Project.....	60
Appendix – E	Structural Drawing of Slab of NDT Project.....	61
Appendix – F	General Arrangement Drawing, Pediatric Project.....	62
Appendix – G	Structural Drawing of Slab of Pediatric Project.....	63
Appendix – H	ICC SBS Slab Drawing of Commercial building, at Nugegoda.....	64